



**ADDENDUM NO. 3-REV-1**  
**April 11, 2022**

**PROJECT: Jerome Elementary School**  
**Jerome School District**  
**Jerome, Idaho**

The following addenda apply to the Drawings and/or Specifications for this project and shall be a part of the Contract Documents.

**PROJECT MANUAL**

**SPECIFICATION SECTION 087100 – DOOR HARDWARE**

1. Revise hardware group for Door C123b:

**Set: 33.0**

Doors: C123b

3 Hinge, Full Mortise, Hvy Wt	<u>T4A3786 NRP</u>	US26D	MK
1 Passage Latch	<u>10XU15 LL</u>	US26D	SA
1 Magnetic Lock	<u>M82BD</u>		SU ↗
1 Gasketing	<u>S88BL</u>		PE
1 Push Button	<u>TS-21R</u>		AK ↗
1 Power Supply	<u>AQD series as req'd</u>		SU ↗

Notes: Door normally allows free ingress and egress. Free egress at all times except when push button that engages magnetic lock is being actively held down. Door unlocks and allows free egress upon fire alarm, loss of power, or when push button is not being held.

SPECIFICATION SECTION 096513 – RESILIENT SHEET FLOORING

1. The following items are in response to bidders' questions and are approved.
  - a. Aluminum Cove Base Accessories are approved in lieu of stainless steel.

**DRAWINGS**

SHEET A4.1

1. Add to the Room Finish Schedule – Area F. The concrete ramps in the Cafetorium shall have a polished concrete finish with 4" rubber base. All stairs to the Stage shall have "RST" resilient stair treads, risers, and base. Refer to Specification Section 096513.

SHEET A4.2

1. Remove Door D111 from the door schedule.

SHEET A5.1-A5.5

1. At metal wall panel locations, aluminum molding joints shall be at 4'-0" o.c. maximum and as approved by the Architect. Moldings shall be mitered.

**Civil Addendum Items**

Refer to EHM Engineers "Addendum No. 3" attached, this and all related documents shall be a part of this addendum and part of the Contract Documents for this Project.

Attachments:

EHM Engineers, Addendum No. 3

**- End of Addendum No. 3 -**



Date: April 11, 2022

Subject: Jerome Elementary School, Irrigation Improvements  
**Addendum No. 3**

The following addendum is being issued for the Civil drawings:

SHEET C-7 (Glen Eagle Subdivision Construction Plans)

1. Pipe specified for the 36" irrigation main is listed as ASTM F679 PS 46 PVC pipe. Due to expected long delivery times or availability, acceptable substitutes that may be used are as follows:

36" diameter (100 psi) PIP (plastic irrigation pipe).  
36" diameter Class III Reinforced Concrete Pipe.

All installation and construction shall be in conformance with Idaho Standards for Public Works Construction 2020 Edition.

---

David Thibault, Engineer of Record

621 North College Rd., Suite 100 • Twin Falls, Idaho 83301 • [208] 734-4888 • Fax [208] 734-6049  
3501 W. Elder St., Suite 100 • Boise, Idaho 83705 • [208] 386-9170 • Fax [208] 386-9076

IN THE FIELDS OF:  
PLANNING • SURVEYING • HIGHWAYS • WATER • SEWAGE • STRUCTURAL • SUBDIVISIONS • BRIDGES • ENVIRONMENTAL • QUALITY CONTROL • CONSTRUCTION MGMT.

Jerome School District - New Jerome Elementary School				
Bids to Starr Corporation by April 14, 2022 at 2:00PM				ADD-03 REVISIONS 4/11/22
Bid Package No.	Package Description	Spec Section	Description	Additional Comments: All items include material, labor, and equipment for installation, unless noted otherwise.
<b>BP-01 CONCRETE (Building, On-Site &amp; Sub-Division Combined)</b>				
	Concrete (Building, On-Site & Sub-Division)	Division 1	General Requirements	All sections to be included in their entirety.
	Concrete (Building, On-Site & Sub-Division)	033000	Cast-In-Place Concrete	Includes all building, On-Site & Sub-Division concrete including reinforcement and embeds. Includes excavation & backfill of building foundations, installation of 3/4" base material under slabs-on-grade, (gravel provided by Site Contractor). Grading for On-Site & Sub-Division concrete by Site Contractor. Curbs, gutters & sidewalk for both On-Site & Sub-Division included.
	Concrete (Building, On-Site & Sub-Division)	071113	Bituminous Dampproofing	Provide for concrete foundation walls.
	Concrete (Building, On-Site & Sub-Division)	072100	Thermal Insulation	Provide for foundation insulation only.
	Concrete (Building, On-Site & Sub-Division)	079200	Joint Sealants	For this scope of work only.
	Concrete (Building, On-Site & Sub-Division)	321313	Concrete Paving	Excludes concrete for Playground Equipment & Site Furnishings. Includes all curb, gutter & sidewalks.
	Concrete (Building, On-Site & Sub-Division)	321726	Tactile Warning Surfacing	As required for this scope of work.
<b>BP-01a CONCRETE (Building &amp; On-Site, only)</b>				
	Concrete (Building & On-Site, only)	Division 1	General Requirements	All sections to be included in their entirety.
	Concrete (Building & On-Site, only)	033000	Cast-In-Place Concrete	Includes all building and site concrete including reinforcement and embeds. Grading for Building & On-Site concrete by Site Contractor. Curbs, gutters & sidewalk for On-Site included.
	Concrete (Building & On-Site, only)	071113	Bituminous Dampproofing	Provide for concrete foundation walls.
	Concrete (Building & On-Site, only)	072100	Thermal Insulation	Provide for foundation insulation only.
	Concrete (Building & On-Site, only)	079200	Joint Sealants	For this scope of work only.
	Concrete (Building & On-Site, only)	321313	Concrete Paving	Excludes concrete for Playground Equipment & Site Furnishings. Includes all curb, gutter & sidewalks.
	Concrete (Building & On-Site, only)	321726	Tactile Warning Surfacing	As required for this scope of work.
<b>BP-01b CONCRETE (Sub-Division, only)</b>				
	Concrete (Sub-Division, only)	Division 1	General Requirements	All sections to be included in their entirety.
	Concrete (Sub-Division, only)	033000	Cast-In-Place Concrete	Includes all Sub-Division concrete including reinforcement and embeds. Grading for Sub-Division concrete by Site Contractor.
	Concrete (Sub-Division, only)	071113	Bituminous Dampproofing	Provide for concrete foundation walls.
	Concrete (Sub-Division, only)	072100	Thermal Insulation	Provide for foundation insulation only.
	Concrete (Sub-Division, only)	079200	Joint Sealants	For this scope of work only.
	Concrete (Sub-Division, only)	321313	Concrete Paving	Excludes concrete for Playground Equipment & Site Furnishings. Includes all curb, gutter & sidewalks.
	Concrete (Sub-Division, only)	321726	Tactile Warning Surfacing	As required for this scope of work.
<b>BP-02 POLISHED CONCRETE FINISHING</b>				
	Polished Concrete Finishing	Division 1	General Requirements	All sections to be included in their entirety.
	Polished Concrete Finishing	033543	Polished Concrete Finishing	
	Polished Concrete Finishing	079200	Joint Sealants	For this scope of work only.
<b>BP-03 MASONRY</b>				
	Masonry	Division 1	General Requirements	All sections to be included in their entirety.
	Masonry	034500	Precast Architectural Concrete	ADD-02: Provide precast concrete caps at masonry walls.
	Masonry	042000	Unit Masonry	Include all masonry reinforcement. Bucks for CMU openings by Others.
	Masonry	079200	Joint Sealants	For this scope of work only.
<b>BP-04 STRUCTURAL STEEL (Supply &amp; Install)</b>				
	Structural Steel	Division 1	General Requirements	All sections to be included in their entirety.
	Structural Steel	051200	Structural Steel Framing	Material supplied, but installed by Others: Steel bollards, steel downspouts, anchor bolts set in concrete or masonry, masonry lintels, embeds and as per Specs. Include grouting of column bases.
	Structural Steel	052100	Steel Joist Framing	
	Structural Steel	053100	Steel Decking	
	Structural Steel	055000	Metal Fabrications	Includes roof ladder, all miscellaneous angles and lintels.
	Structural Steel	055113	Metal Pan Stairs	ADD-01: Delete this spec in its entirety.
	Structural Steel	055213	Pipe and Tube Railings	ADD-03: Include powder-coat finish for Stage Stair Railing shown on details 2, 6 / A3.16; Reference Note 5.14 per ADD-02.
<b>BP-04a STRUCTURAL STEEL (Install, Only)</b>				
	Structural Steel	Division 1	General Requirements	All sections to be included in their entirety.
	Structural Steel	051200	Structural Steel Framing	Material supplied, but installed by Others: Steel bollards, steel downspouts, anchor bolts set in concrete or masonry, masonry lintels, embeds and as per Specs. Include grouting of column bases.
	Structural Steel	052100	Steel Joist Framing	
	Structural Steel	053100	Steel Decking	
	Structural Steel	055000	Metal Fabrications	Includes roof ladder, all miscellaneous angles and lintels.
	Structural Steel	055113	Metal Pan Stairs	ADD-01: Delete this spec in its entirety.
	Structural Steel	055213	Pipe and Tube Railings	
<b>BP-04b STRUCTURAL STEEL (Supply, Only)</b>				
	Structural Steel	Division 1	General Requirements	All sections to be included in their entirety.
	Structural Steel	051200	Structural Steel Framing	Material supplied, but installed by Others: Steel bollards, steel downspouts, anchor bolts set in concrete or masonry, masonry lintels, embeds and as per Specs.
	Structural Steel	052100	Steel Joist Framing	
	Structural Steel	053100	Steel Decking	
	Structural Steel	055000	Metal Fabrications	Includes roof ladder, all miscellaneous angles and lintels.
	Structural Steel	055113	Metal Pan Stairs	ADD-01: Delete this spec in its entirety.
	Structural Steel	055213	Pipe and Tube Railings	ADD-03: Include powder-coat finish for Stage Stair Railing shown on details 2, 6 / A3.16; Reference Note 5.14 per ADD-02.
<b>BP-05 ROUGH CARPENTRY</b>				
	Rough Carpentry	Division 1	General Requirements	All sections to be included in their entirety.
	Rough Carpentry	061000	Rough Carpentry	Includes all wood blocking and wood nailer at top of parapets. Include all framing connectors, (i.e. holdowns, straps, hangers, etc.). Include bucks for all CMU openings.
	Rough Carpentry	061600	Sheathing	
	Rough Carpentry	061753	Shop Fabricated Wood Trusses	
	Rough Carpentry	074243	Composite Wall Panels	
	Rough Carpentry	072700	Infiltration Barriers	

	Rough Carpentry	079200	Joint Sealants	For this scope of work only.
<b>BP-06 MILLWORK</b>				
	Millwork	Division 1	General Requirements	All sections to be included in their entirety.
	Millwork	064116	Plastic Laminate Faced Architectural Cabinets	Includes countertops, window sills, and other miscellaneous laminates per the drawings and specifications. ADD-02: Provide the P-Lam wrapped head, side jambs & door stops for Under-Stage doors, (US). BP-08 to provide the flush wood doors & hardware specified in Addendum-02.
	Millwork	079200	Joint Sealants	Sealants for this scope of work only.
<b>BP-07 ROOFING</b>				
	Roofing	Division 1	General Requirements	All sections to be included in their entirety.
	Roofing	072100	Thermal Insulation	For this scope of work only.
	Roofing	074213	Metal Panels	
	Roofing	075423	Thermoplastic Polyolefin Roofing (TPO)	
	Roofing	076200	Sheet Metal Flashing and Trim	Gutter and gutter sleeve only. Steel downspout by others. Includes metal valley flashing.
	Roofing	077200	Roof Accessories	
	Roofing	079200	Joint Sealants	Sealants for this scope of work only.
<b>BP-08 DOORS &amp; HARDWARE</b>				
	Doors and Hardware	Division 1	General Requirements	All sections to be included in their entirety.
	Doors and Hardware	081113	Hollow Metal Doors and Frames	Includes metal hollow door and window frames, doors, sidelite and borrow lite frames and hardware.
	Doors and Hardware	081416	Flush Wood Doors	ADD-02: Provide the Under-Stage doors, (US), plus the hardware specified in Addendum-02. These doors are a half-high flush wood door at 1 3/4" thick. BP-06 Millwork to provide the P-Lam wrapped head & side jambs plus the door stops.
	Doors and Hardware	087100	Door Hardware	Hardware for this scope of work, only.
	Doors and Hardware	088000	Glazing	ADD-01: Delete this Spec Section from BP-08. All glazing provided by BP-10.
<b>BP-09 OVERHEAD COILING DOORS</b>				
	Overhead Coiling Doors	Division 1	General Requirements	All sections to be included in their entirety.
	Overhead Coiling Doors	083313	Overhead Coiling Doors	
	Overhead Coiling Doors	079200	Joint Sealants	Sealants for this scope of work only.
<b>BP-10 ALUMINUM FRAMED ENTRANCES &amp; STOREFRONTS</b>				
	Aluminum Framed Entrances & Storefronts	Division 1	General Requirements	All sections to be included in their entirety.
	Aluminum Framed Entrances & Storefronts	084113	Aluminum Framed Entrances & Storefronts	
	Aluminum Framed Entrances & Storefronts	084523	Translucent Fiberglass Sandwich Panel Assembly	
	Aluminum Framed Entrances & Storefronts	085619	Pass Thru Windows	
	Aluminum Framed Entrances & Storefronts	087100	Door Hardware	Hardware for this scope of work, only.
	Aluminum Framed Entrances & Storefronts	088000	Glazing	Includes all glass for storefronts & hollow metal doors & frames.
	Aluminum Framed Entrances & Storefronts	079200	Joint Sealants	Sealants for this scope of work only.
<b>BP-11 DRYWALL</b>				
	Drywall	Division 1	General Requirements	All sections to be included in their entirety.
	Drywall	054000	Cold Formed Metal Framing	
	Drywall	066400	Plastic Paneling (FRP)	
	Drywall	072100	Thermal Insulation	Wall, Ceiling & Vapor barrier, only.
	Drywall	078446	Fire Resistive Joint Systems	As applies to the scope of work.
	Drywall	079000	Joint Sealants	Sealants for this scope of work only.
	Drywall	092216	Light Gauge Steel Framing	
	Drywall	092900	Gypsum Board	Provide & install cementitious backer units.
	Drywall	095113	Acoustical Panel Ceilings	
	Drywall	097723	Fabric Wrapped Panels	
	Drywall	098413	Fixed Sound Absorptive Panels	
<b>BP-12 WOOD ATHLETIC FLOORING</b>				
	Wood Athletic Flooring	Division 1	General Requirements	All sections to be included in their entirety.
	Wood Athletic Flooring	096466	Wood Athletic Flooring	Includes hardwood flooring at Stage F101.
	Wood Athletic Flooring	079000	Joint Sealants	Sealants for this scope of work only.
<b>BP-13 TILING</b>				
	Tiling	Division 1	General Requirements	All sections to be included in their entirety.
	Tiling	093013	Tiling	Cementitious backer units by Drywall bid package.
	Tiling	079000	Joint Sealants	Sealants for this scope of work only.
<b>BP-14 FLOOR COVERING</b>				
	Flooring	Division 1	General Requirements	All sections to be included in their entirety.
	Flooring	096513	Resilient Base and Accessories	
	Flooring	096516	Resilient Sheet Flooring	Joint and crack filling, minor leveling, and sanding is included.
	Flooring	096519	Resilient Tile Flooring (LVT)	Joint and crack filling, minor leveling, and sanding is included.
	Flooring	096816	Carpeting	Joint and crack filling, minor leveling, and sanding is included.
	Flooring	079000	Joint Sealants	All joints between materials installed under this scope and adjacent finishes
<b>BP-15 PAINTING</b>				
	Painting	Division 1	General Requirements	All sections to be included in their entirety.
	Painting	099113	Exterior Painting	ADD-02: Prime & paint in entirety all roof top equipment, vents & flues extending above top of parapet elevation that are not factory-finished, (REF: Elevation Plans A5.1 plus). DELETE REFERENCE TO "NOT FACTORY FINISHED" and paint everything that extends above the top of parapet.
	Painting	071900	Water Repellents	Seal all exterior masonry surfaces with water repellent sealer / anti-graffiti coating.
	Painting	097200	Digitally Printed Vinyl Wallcovering Murals	
	Painting	099123	Interior Painting	Includes labor and materials to seal the concrete floors indicated in the Room Finish Schedule, (A4.1 & Spec 099123). ADD-01: Include field-painting of Tectum Panels, (REF: Spec 098413-2; A; 1).
	Painting	099600	High Performance Coatings	All exposed-to-view structural steel both interior & exterior.
	Painting	079000	Joint Sealants	All interior sealants exclusive of concrete, aluminum storefront, and millwork. Includes caulking hollow metal frames prior to painting.
<b>BP-16 SPECIALTIES</b>				
	Specialties	Division 1	General Requirements	All sections to be included in their entirety.
	Specialties	083513	Accordion Folding Partition	
	Specialties	101100	Visual Display Surfaces	
	Specialties	101416	Signage	
	Specialties	102113	Toilet Compartments	
	Specialties	102123	Cubicle Curtains	

	Specialties	102600	Wall & Door Protection	
	Specialties	102800	Toilet & Bath Accessories	Labor for Toilet Paper, Paper Towel & Soap Dispensers, Owner Furnished & Contractor Installed.
	Specialties	104413	Fire Extinguisher Cabinets	Provide & install Knox Box listed in this Specification.
	Specialties	104416	Fire Extinguishers	
	Specialties	105113	Metal Lockers	
	Specialties	107000	Exterior Sun Control Devices	
	Specialties	115213	Projection Screens	
	Specialties	116143	Platform Curtains	
	Specialties	323190	Flagpole	
	Specialties	079000	Joint Sealants	Sealants for this scope of work only.
<b>BP-17 FOOD SERVICE EQUIPMENT</b>				
	Food Service Equipment	Division 1	General Requirements	All sections to be included in their entirety.
	Food Service Equipment	113013	Residential Appliances	Provide & install all Residential Appliances specified.
	Food Service Equipment	114000	Food Service Equipment	Provide & install all Food Service Equipment specified.
<b>BP-18 GYMNASIUM EQUIPMENT</b>				
	Gymnasium Equipment	Division 1	General Requirements	All sections to be included in their entirety.
	Gymnasium Equipment	116600	Wall & Floor Padding	
	Gymnasium Equipment	116623	Gymnasium Equipment	
<b>BP-19 HORIZONTAL LOUVER BLINDS</b>				
	Horizontal Louver Blinds	Division 1	General Requirements	All sections to be included in their entirety.
	Horizontal Louver Blinds	122213	Horizontal Louver Blinds	
<b>BP-20 TELESCOPING STANDS</b>				
	Telescoping Stands	Division 1	General Requirements	All sections to be included in their entirety.
	Telescoping Stands	126600	Telescoping Stands	
<b>BP-21 FIRE SPRINKLER SYSTEM</b>				
	Fire Sprinkler System	Division 1	General Requirements	All sections to be included in their entirety.
	Fire Sprinkler System	210000	Fire Sprinkler Systems	
	Fire Sprinkler System	078413	Penetration Firestopping	As required for this scope of work.
	Fire Sprinkler System	078413	Firestopping Appendix A	As required for this scope of work.
	Fire Sprinkler System	078446	Fire Resistive Joint Systems	As required for this scope of work.
	Fire Sprinkler System	079200	Joint Sealants	As required for this scope of work.
	Fire Sprinkler System	083113	Access Doors and Frames	Supply and install as needed for access to items installed under this scope of work.
<b>BP-22 PLUMBING</b>				
	Plumbing	Division 1	General Requirements	All sections to be included in their entirety.
	Plumbing	220000	Plumbing General Requirements	
	Plumbing	220100	Plumbing	
	Plumbing	220800	Commissioning of Plumbing	
	Plumbing	078413	Penetration Firestopping	As required for this scope of work.
	Plumbing	078413	Firestopping Appendix A	As required for this scope of work.
	Plumbing	078446	Fire Resistive Joint Systems	As required for this scope of work.
	Plumbing	079200	Joint Sealants	As required for this scope of work.
	Plumbing	083113	Access Doors and Frames	Supply and install as needed for access to items installed under this scope of work.
<b>BP-23 HVAC</b>				
	HVAC	Division 1	General Requirements	All sections to be included in their entirety.
	HVAC	230000	HVAC General Requirements	
	HVAC	230100	Heating, Ventilating and Air Conditioning	
	HVAC	230150	Mechanical Start-Up	
	HVAC	230593	Testing, Adjusting, and Balancing for HVAC	
	HVAC	230800	HVAC Commissioning Requirements	
	HVAC	230900	Direct Digital Control System	
	HVAC	078413	Penetration Firestopping	As required for this scope of work.
	HVAC	078413	Firestopping Appendix A	As required for this scope of work.
	HVAC	078446	Fire Resistive Joint Systems	As required for this scope of work.
	HVAC	079200	Joint Sealants	As required for this scope of work.
	HVAC	083113	Access Doors and Frames	Supply and install as needed for access to items installed under this scope of work.
<b>BP-24 ELECTRICAL</b>				
	Electrical	Division 1	General Requirements	All sections to be included in their entirety.
	Electrical	260500	Electrical General Provisions	
	Electrical	260501	Field Test and Operational Check	
	Electrical	260502	Coordination Study	
	Electrical	260519	Conductors and Cables	
	Electrical	260526	Grounding	
	Electrical	260529	Supporting Devices	
	Electrical	260533	Raceways and Boxes	
	Electrical	260536	Cable Trays	
	Electrical	260543	Under Slab and Underground Electrical Work	
	Electrical	260800	Lighting Systems Commissioning	
	Electrical	260923	Lighting Control Devices	
	Electrical	262200	Dry-Type Transformers	
	Electrical	262413	Switchboards	
	Electrical	262416	Panelboards	
	Electrical	262726	Wiring Devices	
	Electrical	262813	Fuses	
	Electrical	262815	Disconnect Switches	
	Electrical	264314	Transient Voltage Surge Suppression	
	Electrical	265100	Interior Lighting	
	Electrical	265600	Exterior Lighting	Include concrete light pole bases, excavation, backfill & compaction.
	Electrical	271101	Telecom Raceway Systems	
	Electrical	271500	Telecommunication Cabling	ADD-02: Include this section in its entirety.
	Electrical	275116	Integrated Communications and Clock Network	
	Electrical	275117	Sound Systems	
	Electrical	275200	Classroom Audio System	
	Electrical	281000	Access Control System	
	Electrical	282310	Video Management System	
	Electrical	282329	Video Surveillance Remote Devices and Sensors	
	Electrical	283200	Voice Evacuation Fire Alarm System	
	Electrical	078413	Penetration Firestopping	As required for this scope of work.

	Electrical	078413	Firestopping Appendix A	As required for this scope of work.
	Electrical	078446	Fire Resistive Joint Systems	As required for this scope of work.
	Electrical	079200	Joint Sealants	As required for this scope of work.
	Electrical	083113	Access Doors and Frames	Supply and install as needed for access to items installed under this scope of work.
<b>BP-25 SITEWORK (On-Site &amp; Sub-Division Combined)</b>				
	Sitework (On-Site & Sub-Division Combined)	Division 1	General Requirements	All sections to be included in their entirety. <b>Refer to both the On-Site and Glen Eagle Sub-Division Civil drawings.</b>
	Sitework (On-Site & Sub-Division Combined)	310120	Traffic Control Requirements	As required for this scope of work for both On-Site & Sub-Division Sitework.
	Sitework (On-Site & Sub-Division Combined)	311000	Site Clearing	Includes erosion controls for both On-Site & Sub-Division Sitework
	Sitework (On-Site & Sub-Division Combined)	312000	Earth Moving	Provide base material for Building interior slabs-on-grade. Placed by Concrete Contractor. Building foundation excavation & backfill by Concrete Contractor. Excavation & backfill for On-Site & Sub-Division cast-in-place structures included. Gravel & grading for On-Site & Sub-Division concrete included. Includes grading, gravel & asphalt.
	Sitework (On-Site & Sub-Division Combined)	315000	Excavation Support & Protecton	Include for both On-Site & Sub-Division Sitework.
ADD-01	Sitework (On-Site & Sub-Division Combined)	Glen Eagle Sub-Division & On-Site Civil drawings	On & Off-Site Utilities	Provide all utilities both On-Site & Sub-Division as shown on On-Site & Glen Eagle Sub-Division Civil drawings. This work excludes the Production & Injection wells, but includes all piping to and from those wells to the building. Includes Fire Service Line from Main to inside MECH E111 up through slab including flange connection. Includes Water Service Line from Main to inside MECH E111 up through slab, including flange connection.
	Sitework (On-Site & Sub-Division Combined)	321723	Pavement Markings	Includes parking lot striping, handicap stalls, directional arrows, fire lane markings. Excludes striping for playground area games.
	Sitework (On-Site & Sub-Division Combined)	323150	Site Signage	Includes all site signage, either pole, fence or building mounted.
	Sitework (On-Site & Sub-Division Combined)	Appendix A	Geotechnical Report	Provide a unit price on Site Work bid form for rock excavation.
<b>BP-25a SITEWORK (On-Site, Only)</b>				
	Sitework (On-Site, Only)	Division 1	General Requirements	All sections to be included in their entirety. <b>Refer to the On-Site Civil drawings.</b>
	Sitework (On-Site, Only)	310120	Traffic Control Requirements	As required for this scope of work for On-Site Sitework, only.
	Sitework (On-Site, Only)	311000	Site Clearing	Includes erosion controls for On-Site Sitework, only.
	Sitework (On-Site, Only)	312000	Earth Moving	Provide base material for Building interior slabs-on-grade. Placed by Concrete Contractor. Building foundation excavation & backfill by Concrete Contractor. Includes grading, gravel & asphalt.
	Sitework (On-Site, Only)	315000	Excavation Support & Protecton	Include for On-Site Sitework, only.
ADD-01	Sitework (On-Site, Only)	On-Site Civil drawings	On-Site Utilities	Includes all utilities. Connect to stub-ins provided by Sub-Division Contractor. This work excludes the Production & Injection wells, but includes all piping to and from the wells to the building. Includes Fire Service Line from Main to inside MECH E111 up through slab including flange connection. Includes Water Service Line from Main to inside MECH E111 up through slab, including flange connection.
	Sitework (On-Site, Only)	321723	Pavement Markings	Includes parking lot striping, handicap stalls, directional arrows, fire lane markings. Excludes striping for playground area games.
	Sitework (On-Site, Only)	323150	Site Signage	Includes all site signage, either pole, fence or building mounted.
	Sitework (On-Site, Only)	Appendix A	Geotechnical Report	Provide a unit price on Site Work bid form for rock excavation.
<b>BP-25b SITEWORK (Sub-Division, Only)</b>				
	Sitework (Sub-Division, Only)	Division 1	General Requirements	All sections to be included in their entirety. <b>Refer to the Glen Eagle Sub-Division Civil drawings.</b>
	Sitework (Sub-Division, Only)	310120	Traffic Control Requirements	As required for this scope of work for Sub-Division Sitework, only.
	Sitework (Sub-Division, Only)	311000	Site Clearing	Includes erosion controls for Sub-Division Sitework, only.
	Sitework (Sub-Division, Only)	312000	Earth Moving	Gravel & grading for On-Site & Sub-Division concrete included. Includes grading, gravel & asphalt.
	Sitework (Sub-Division, Only)	315000	Excavation Support & Protecton	Include for Sub-Division Sitework, only.
	Sitework (Sub-Division, Only)	Glen Eagle Sub-Division Civil drawings	On-Site Utilities	Includes all utilities stubbed into the building site as shown on drawings.
	Sitework (Sub-Division, Only)	321723	Pavement Markings	As required for this scope of work.
	Sitework (Sub-Division, Only)	323150	Site Signage	As required for this scope of work.
	Sitework (Sub-Division, Only)	Appendix A	Geotechnical Report	Provide a unit price on Site Work bid form for rock excavation.
<b>BP-27 PLAYGROUND EQUIPMENT &amp; STRUCTURES</b>				
	Playground Equipment & Structures	Division 1	General Requirements	All sections to be included in their entirety.
	Playground Equipment & Structures	321800	Playground Equipment and Structures	REF: SD2.1 - Playground EQ Lists. Includes all concrete for this scope of work.
	Playground Equipment & Structures	321822	Synthetic Playground Turf	
<b>BP-28 SITE FURNISHINGS</b>				
	Site Furnishings	Division 1	General Requirements	All sections to be included in their entirety.
	Site Furnishings	323300	Site Furnishings	Provide and install all items in this Spec Section. Includes concrete, bases & anchoring for all equipment along with striping.
<b>BP-29 CHAIN-LINK &amp; DECORATIVE FENCES</b>				
	Chain-Link & Decorative Fences	Division 1	General Requirements	All sections to be included in their entirety.
	Chain-Link & Decorative Fences	323113	Chain Link Fences and Gates	
	Chain-Link & Decorative Fences	323119	Decorative Metal Fences and Gates	
<b>BP-30 LANDSCAPE &amp; IRRIGATION</b>				
	Landscape & Irrigation	Division 1	General Requirements	All sections to be included in their entirety.
	Landscape & Irrigation	328400	Landscape Irrigation	
	Landscape & Irrigation	328500	Landscape Grading	Site will be cut to sub-grade elevation, (+/-) one-tenth by Others.
	Landscape & Irrigation	329113	Soil Preparation	
	Landscape & Irrigation	329200	Turf and Grasses	
	Landscape & Irrigation	329290	Tree Protection and Trimming	
	Landscape & Irrigation	329300	Plants	